

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Construction of Culverts and Improvements to drain Bharatnagar cross road in Ward No.06 Byatarayanapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	124.80	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	215.28	Rupees Two Hundred Fifteen and Twenty Eight Paise Only
2	21.00	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	5680.61	Rupees Five Thousand Six Hundred Eighty and Sixty One Paise Only
3	2.88	Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	Tn	80146.60	Rupees Eighty Thousand One Hundred Forty Six and Sixty Paise Only
4	43.70	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	7422.99	Rupees Seven Thousand Four Hundred Twenty Two and Ninety Nine Paise Only
5	90.90	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	28.80	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕಿ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ